BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Name of work: Detailed Estimate for the Work of Improvements of Roads and Drains at Shabarinagara in Ward No. 06 Byatarayanapura Sub Division

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	900.00	KSRRB 300-1. Earth work excavation by manual means in **hard soil** involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.MORTH chapter 3. No. 126/ Item No. 19.2/ PWD SR 2011-12 For Rachenahalli Tank	**Cum**	115.56	
2	900.00	Hegadenagara 5th Cross	**Cum**	115.56	
3	2690.00	Code 0516- Providing Palstic Sheet (Page No.XXII/1.612 PWD SR 2014-15For Rachenahalli Tank	**Sqm**	6	
4	487.20	Providing Stone dust to approch road and near immerssion tank for levelling and to protect not to sliping Sl No.23 Code 400 Metal Component Page No I SR 2010-11 For Rachenahalli Tank	Cum	750	
5	35.00	Hire Charge of Pumping water 3.5 KL/hr Capacity Pump For Rachenahalli Tank	Hrs	50	
6	35.00	Hegadenagara 5th Cross	Hrs	50	
7	450.00	Engaging unskilled heavy Mazdoor labour for Guarding and for helping the public to Immersion tank Ganesh Idols and to safe guard the public during the pooja Time For Rachenahalli Tank	Days	243.55	
8	450.00	Hegadenagara 5th Cross	Days	243.55	
9	1750.00	Hire Charges for Shamiyana **Side wall** of 8ft Hight **(Size175 Rft) For Rachenahalli Tank**	**Rtr**	17	
10	1750.00	Hegadenagara 5th Cross	**Rtr**	17	
11	150.00	Hire Charges for Armless Plastic Charis For Rachenahalli Tank	No	4	
12	150.00	Hegadenagara 5th Cross	No	4	
13	150.00	Hire Charges for Wooden Table of size 6ft x 2ft For Rachenahalli Tank	No	40	
14	150.00	Hegadenagara 5th Cross	No	40	
15	1100.00	Hire Charge for supplying and running circuit service main with necessary messanger wire and reel insulators and maintaining the same 4 of 25 sqmm PVC insulated and sheathedaluminium wire (KPWD Electrical SR 2011-12 P.55/I.6 III b) For Rachenahalli Tank	Day	9	
16	1100.00	Hegadenagara 5th Cross	Day	9	
17	80.00	1321 Hire charge of 100 KVA Generator including operator.Fuel transporation nd Handling charges PWD SR 2011-12 XVI/I.92)For Rachenahalli Tank	Hrs	630	
18	80.00	Hegadenagara 5th Cross	Hrs	630	
19	20.00	Hire Charges for Flood Lighting Arrangements for the stage and existing Immersion Tank during night time For Rachenahalli Tank	Each	285	
20	20.00	Hegadenagara 5th Cross	Each	285	
21	3432.00	Hire Charges for Three Tier Barricading with Casurens poles at 2.50mtrs C/C Vertically and 0.50 mtrs C/C Horizontally with Necessary earth work and labour For Rachenahalli Tank	Rtr	17	

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
22	3432.00	Hegadenagara 5th Cross	Rtr	17	
23	[redacted]00.00	Hire Charge for Shamiyana with Necessary Bambo Poles.Erection charges including transportation -(Size: 40ft x30ft=1200 sqft) For Rachenahalli Tank	Sft	3	
24	13200.00	Hegadenagara 5th Cross	Sft	3	
25	25.00	Hire Charge of Pumping water 3.5 KL/hr Capacity Pump For Rachenahalli Tank	Hrs	50	
26	25.00	Hegadenagara 5th Cross	Hrs	50	
27	113.00	Retro - Reflectorised Traffic Signs :- Providing and fixing of retro - reflectorised cautionary, mandatory and informatory sign as per IRC : 67 - 2001 made of high intensity grade micro prismatic HIP type IV sheeting, fixed over alumium sheeting, 12 gauge thick supported on 75mm dia and 4mm thick MS pipe 2.8 mtres long firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 45cms x 45cm x 60cm, 60 cm below ground level as per approved drawing. The item includes earthwork excavation, Cement Concrete M-15 grade, 2 coats of approved colour synthetic enamel painting to the steel surface, as per clauses, including curing, cost of all materials, labour, loading, unloading, lead, lift, transporting etc., complete. **(P.No.65, I.No.8.04 of NH SR 2009-10)**	Each	3391.2	

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92
28/12/15

Note:

1. Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
2. Unit rates and prices shall be quoted by the Tender in Indian rupees.
3. Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)
4. Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

ಕರಡು ಟೆಂಡರ್ ಪಡ್ಯೂಲ್‌ನ್ನು
ಪರಿಷ್ಕರಿಸಿಗಳ ಸಂಖ್ಯೆ.....( )
ಪರಿಷ್ಕರಿಸಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಿದಾಗಿದೆ

Superintending Engineer
Yelahanka Zone
BBMP, Bangalore